

Sample Construction Survey Report

Layout, as-built verification, concrete slabs and steel works

Report Overview

This sample shows the structure and level of detail OnPoint can provide for construction survey deliverables. Values, project names and checks shown here are demonstration data only.

Prepared by

OnPoint Geomatics - Eindhoven, NL

Contact

info@onpointgeo.nl | +31 6 1468 6059

Project Snapshot

Project	Industrial slab / steel layout
Location	Eindhoven, NL
Date	22 June 2026
Coordinate basis	Local site grid
Instrument	Trimble S5 + TSC7

Included Deliverables

- Control network verification
- Concrete slab layout and stakeout notes
- Steel grid / base plate verification
- As-built point schedule with tolerances
- QA notes and recommended actions

Accuracy Statement

Field observations are controlled against verified site control and reported with practical construction tolerances. Final accuracy depends on control quality, site access, atmospheric conditions and the requested deliverable.

Typical use: high accuracy layout, as-built verification and civil works coordination.

Survey Control and Site Grid

Control points were checked before stakeout and again after the measurement run. The sample grid below illustrates how critical slab and steel points are reported for quick site review.



Sample As-Built Point Schedule

Point	Item	Design X	Design Y	Delta X	Delta Y	Delta Z	Status
P01	Grid A/1	100.000	200.000	+2	-1	+1	OK
P04	Slab edge	112.500	200.000	+3	+2	0	OK
P08	Anchor group	125.000	212.500	-4	+1	+2	OK
P12	Control check	100.000	225.000	+1	-2	+1	OK
P16	Base plate	125.000	225.000	+7	+3	+5	Review
P19	Steel grid	137.500	212.500	-2	+2	+2	OK

Coordinate values and deltas are sample millimetre/site-grid values for demonstration.

Methodology

1

Verify control

Site control is checked against known points before layout or as-built work starts. Any movement or inconsistency is flagged before production measurements.

2

Measure critical geometry

Concrete slab edges, grid intersections, anchor groups and steel base plates are observed using total station workflows suited for high accuracy construction work.

3

Compare against design

Measured positions are compared with issued-for-construction drawings or agreed site-grid coordinates, then summarized by status and recommended action.

Example Floor Level Heatmap



Deliverable Package

- PDF report for review and archive
- Point list in CSV or project format
- Marked-up drawing or control sketch
- Photos or notes where site access affects checks

Notes and Limitations

This sample report is intended to demonstrate report style and content only. A real report is prepared from project-specific drawings, control information, site observations and agreed tolerance requirements. Certified deliverables can include additional signatures, revision records and client-specific formats.

OnPoint Geomatics

info@onpointgeo.nl | +31 6 1468 6059

Prepared for

Sample Client / Project Team